



TENDER

Helipad - Ear Falls, Ontario

The Township of Ear Falls is posting this tender for the construction of a new helipad in Ear Falls Ontario (adjacent to 2 Willow Crescent). This project includes the development of the helipad, supply and installation of perimeter fencing, installation of supplied lighting and controls and associated work. A complete Scope of Work is attached.

Work must be completed by August 30, 2018. Failure to complete the work by the required deadline may result in financial penalties to the proponent for each day the project remains incomplete beyond August 30, 2018.

Submissions must include the following:

- Letter of Interest identifying:
 - A statement indicating that the Contractor will ensure the project will be completed in accordance with the Scope of Work, the Workplace Safety and Insurance Act and Ontario Occupational Health and Safety Act and Regulations
 - A list of any subcontractors that will be used
 - Total Cost for completion of work; HST must be clearly identified.
 - Timeline for the completion of work
- Certificate of Insurance
- WSIB Clearance Certificate

Sealed submissions clearly marked "Tender- Helipad - Ear Falls, Ontario" will be received by email to kballance@ear-falls.com or by mail to the Township of Ear Falls, P.O. Box 309, 2 Willow Crescent, Ear Falls, ON, P0V 1T0, until:

11:00 a.m. local time on Thursday, May 17, 2018

For further information please contact Clerk Treasurer Administrator at 807-222-3624 ext. 27 or by email at kballance@ear-falls.com.

The lowest or any proposal not necessarily accepted. The Corporation reserves the right to reject any or all quotes, to waive, irregularities and informalities therein, and to award any contract in the best interests of the Corporation in its sole unfettered discretion.

The Corporation of the Township of Ear Falls
Kimberly Ballance, Clerk Treasurer Administrator
P.O. Box 309, 2 Willow Crescent
Ear Falls, ON, P0V 1T0
Ph: (807) 222-3624 ext. 27 Fax: (807) 222-2384
kballance@ear-falls.com

TENDER

Helipad - Ear Falls, Ontario

Scope of Work:

- Contractor is responsible to verify all measurements and secure all required locates.
- Construct a 9 m x 9 m square helipad: 200 mm slab with 600 mm club footing/rebar, floating slab design, on 600 mm compacted granular A with weeping tile below. Shall have a roughened pavement finish to provide a skid-resistant surface for helicopters and non-slippery footing for people.
- Install 1.4 m high perimeter fence - 29 m x 29 m with 4.8 m gate opening to provide a 29 m x 29 m safe area surrounding the concrete helipad
- Cut down and remove selected trees/stumps, and landscape affected areas
- Install supplied controls, perimeter and approach lighting according to Transport Canada's regulations. An ESA permit is required will be the responsibility of the contractor.
- Landscape and sod area inside perimeter fence
- Upgrade existing driveway access to helipad with A base.
- Clean-up site of all debris.
- Public safety and site cleanliness shall be ensured at all times.