



REQUEST FOR QUOTE

Wastewater Treatment Plant Roof Replacement - Ear Falls, Ontario

The Township of Ear Falls is requesting Quotes for the supply and install new truss roof system complete with metal roofing over the existing flat roof. A complete Scope of Work is attached. Work must be completed by September 29, 2017.

Work must comply with the Ontario Building Code. Building Permits have been acquired by the Township of Ear Falls for this purpose.

Submissions must include the following:

- Letter of Interest identifying:
 - A statement indicating that the Contractor will ensure the project will be completed in accordance with the Scope of Work, the Workplace Safety and Insurance Act and Ontario Occupational Health and Safety Act and Regulations
 - Total Cost for completion of work per location; HST must be clearly identified.
 - Timeline for the completion of work
- Certificate of Insurance
- WSIB Clearance Certificate

Sealed submissions clearly marked "Quote – Wastewater Treatment Plant Roof Replacement – Ear Falls, Ontario" will be received by email to pdyck@ear-falls.com or mail to the Township of Ear Falls, P.O. Box 309, 2 Willow Crescent, Ear Falls, ON, PoV 1To, until:

11:00 a.m. local time on Wednesday, April 25, 2017

For further information please contact Public Service and Operations Supervisor, Perry Dyck at 807-727-7136 or by email at pdyck@ear-falls.com.

The lowest or any quote not necessarily accepted. The Corporation reserves the right to reject any or all quotes, to waive, irregularities and informalities therein, and to award any contract in the best interests of the Corporation in its sole unfettered discretion.

The Corporation of the Township of Ear Falls
Perry Dyck, Public Service and Operations Supervisor
P.O. Box 309, 2 Willow Crescent
Ear Falls, ON, PoV 1To Ph: (807) 727-7136 Fax: (807) 222-2384

REQUEST FOR QUOTE

Wastewater Treatment Plant Roof Replacement - Ear Falls, Ontario

Scope of Work:

- The site can be viewed at 44 Chestnut Street, Ear Falls, Ontario.
- Mandatory Site meeting on April 12, 2017
- Contractor is responsible to verify all measurements.
- Supply and Install truss roof 5/12 slope with 24" overhang, 2x6 fascia
- Install new coloured metal 26 gauge (tough rib) roof with ice guards (colour to be selected by the Township of Ear Falls)
- New metal Facia, metal soffit and 5" metal gutters
- Removal of existing roof ventilation duct.
- Remove and reinstall radio tower.
- Gables to be finished with metal to match roof.
- Attic Assess installed on West gable
- Blown-in Insulation to R-40
- Removal of water damaged insulation
- All work to meet or exceed Ontario Building Code and is subject to inspection and approval of the Building Inspector.
- Clean-up site of all debris.
- Public safety shall be ensured at all times.